

SURVEY & REMONUMENTATION

FEB 13 2001

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

50408

STATE OF MICHIGAN
Branch County
Recorded

12-15-2000 14:05:13

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

SECTION

*For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
BUTLER TWP		
1. Public Land Survey	T <u>5 S</u> R <u>5 W</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber **00004** Page **0114**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E.R. Reed, P.S.
E.R. REED, Co. REP.

I, EDWARD W. REED, in a field survey on NOV. 2, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NORTHWEST CORNER OF SECTION 30, BUTLER TOWNSHIP, BRANCH COUNTY, MICHIGAN

A. Description of original monument and accessories and/or subsequent restoration:

1825: ROBT CLARK, JR-CORNER SET
1861: KNOWLES-STONE & COBBLES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND COBBLES AND BRICK AT SHALLOW DEPTH-NO STONE, POINT FITS FENCELINE RUNNING NORTH
ACCEPTED AS BEST EVIDENCE OF CORNER
SET 1/2" X 18" REBAR IRON WITH CAP IN CAST IRON MONUMENT BOX WITH ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON WITH CAP IN CAST IRON MONUMENT BOX WITH ROAD SURFACE
GIRARD CORNER NORTH 36 LINKS
6" PIPE ANCHOR POST NORTH 31.88'
TELEPHONE PEDESTAL N21W 53.1'
CENTER OF STAND PIPE S63W 27.6'
EAST END OF ROAD CULVERT S14E 38.9'
IN LINE WITH FENCELINE RUNNING NORTH

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED

DATED: NOV. 2, 2000

Surveyor's Michigan License No. 33985



NOTICE
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995
THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAP- PING PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED. SEND PUBLIC TO REGISTER OF DEEDS FOR COPIES.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E.R. Reed, P.S.
E.R. REED, Co. REP.