

RECORDED

# 42138

FEB 02 2000

BRANCH COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
BUTLER TWP		
1. Public Land Survey	T <u>5</u> S R <u>5</u> W	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN  
Branch County  
Recorded

12-30-1999 11:00:54

Linda Lee Morrison-Mathews

REGISTERED LIBER 000046 Page 0050

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON DEC. 07, 1999

E.R. Reed, P.S.  
E.R. REED

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on OCT. 21, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHWEST CORNER OF SECTION 30  
NORTHWEST CORNER OF SECTION 31

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: JOHN MULLETT, D.S., SET GIRARD CORNER  
1826: ROBT. CLARK, JR., D.S., SET BUTLER CORNER, 44 LINKS SOUTH OF GIRARD CORNER


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" X 6" STONE 18" DEEP  
SET REMON CAP ON 1/2" X 8" REBAR OVER STONE IN CAST IRON MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 8" REBAR WITH REMON CAP IN CAST IRON MONUMENT BOX	
S65E 43.46'	SPIKE N SIDE ROUND WOOD ANCHOR POST
N30E 46.58'	TOP CENTER OF SQUARE ANCHOR POST
N15W 67.97'	TOP CENTER OF SQUARE ANCHOR POST
S85W 63.88'	SPIKE N SIDE POWER POLE
NORTH 30.18'	GIRARD CORNER M-11
19' S	OF CENTERLINE E-W GRAVEL ROAD

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Edward W. Reed  
EDWARD W. REED

Date OCT. 21, 1999

Surveyor's Michigan License No. 33985