

SURVEY & REMONUMENTATION

FEB 08 1999

SECTION

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
<u>BUTLER TWP</u>		
1. Public Land Survey	<u>T 5 S R 5 W</u>	<u>D-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
Branch County
Recorded

11-04-1998 15:46:22

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
9-09-1998

E.R. Reed Co. Rep.
E.R. REED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 14, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 5 & 8

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: R. CLARK, JR., D.S.- CORNER SET
- 1911: WW COX, DEPT CO SURVEYOR - SET GAS PIPE 1 1/2" X 24: LONG, GLASS & PIECES OF BRICK
- 1977: E.R. REED, CO SURVEYOR - FOUND IRON PIPE 24" DEEP WITH 1/2" X 24: REBAR IRON IN CENTER OF PIPE, RECORDED IN LCRC # 206

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN PIPE AS DESCRIBED AND FITTING WITNESS OF LCRC # 206

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET REMON CAP ON TOP OF IRON, SET CI-MONUMENT BOX 3" BELOW GRAVEL ROAD SURFACE

AT NORTH SHOULDER OF ROAD
11.2' NORTH OF C/L OF HERRICKSVILLE ROAD
48" DOUBLE OAK S 27 E 68.2' TO CENTER
TEL PED S 35 W 61.9' TO FACE
CONC CULVERT SUPPORT S 11 E 47.0' TO TOP CENTER
10" ASH N 74 E 48.6' TO CENTER
CONC. CULVERT SUPPORT S 21 W 47.1' TO TOP CENTER

AND IS ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W, REED

Date SEPTEMBER 9, 1998

Surveyor's Michigan License No. 33985

Liber 00003 Page 0213

