

# SURVEY & REMONUMENTATION

FEB 13 2001

## BRANCH COUNTY REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

12-15-2000 14:05:27

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

### SECTION

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
<u>BUTLER TWP</u>		
1. Public Land Survey	<u>T 5 S R 5 W</u>	<u>E-7</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous	S <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
Property in Sec.	S <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>

Liber **00004** Page **0115**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on NOV. 1, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 16, 17, 20 & 21, BUTLER TWP., BRANCH COUNTY, MI

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: ROBT CLARK, JR-CORNER SET  
1855: KNOWLES-SURVEY-NO NOTES OF CORNER

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E. R. Reed, P.S.  
E. R. REED, C. REP.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE, BRICK & GLASS  
SET 1/2" X 17" IRON OVER STONE WITH REMON CAP IN CAST IRON BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 17" REBAR IRON WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE  
TELEPHONE PEDESTAL N44W 60.25'  
POWER POLE (TAG N SIDE) S23E 67.35'  
TELEPHONE PEDESTAL N32E 50.2'  
RR TIE POST N71W 117.0'  
4" PINE S69E 99.3'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Edward W. Reed  
EDWARD W. REED

DATED: NOV. 1, 2000

Surveyor's Michigan License No. 33985

THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAP- PING PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED SEND PUBLIC TO REGISTER OF DEEDS FOR COPIES.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995