

SURVEY & REMONUMENTATION

FEB 13 2001

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

STATE OF MICHIGAN
Branch County
Recorded

09-26-2000 10:16:38

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0097**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON

Aug 9, 2000

E.R. Reed
E.R. REED, Co. Rep.

For corners in

<u>BRANCH COUNTY</u> BUTLER TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>5</u> S R <u>5</u> W	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 3, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 27, 28, 33 & 34, BUTLER TWP.

A. Description of original monument and accessories and/or subsequent restoration:

1825: ROB'T CLARK, CORNER SET
1878: M. KNOWLES, PLANTED PLOW LAND SIDE
COUNTY SURVEYOR NOTES INDICATE "STONE"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND LARGE STONE 26" DEEP IN CENTER OF ROAD IN LINE WITH FENCELINE RUNNING SOUTH
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON MONUMENT BOX OVER STONE 4" BELOW GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON MONUMENT BOX		
FACE OF 10" DIAMETER WOOD ANCHOR POST	SOUTH	35.1'
NEAR FACE OF 16" WALNUT	N24W	32.3'
NEAR FACE OF 12" MAPLE	N38E	33.4'
NEAR FACE OF 12' HICKORY	N16W	27.8'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*

EDWARD W. REED

DATED: JULY 3, 2000

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

