

SURVEY & REMONUMENTATION

FEB 13 2001

SECTION

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

09-26-2000 10:16:49

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0098

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
Aug 9, 2000

E. R. Reed
E.R. REED, Co. Rep.

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
BUTLER TWP		
1. Public Land Survey	<u>T 5 S R 5W</u>	<u>H-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 3, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: ROB'T CLARK, JR, CORNER SET
- 1878: M. KNOWLES, PLOW POINT
- OLD NOTES OF COUNTY SURVEYOR INDICATED "STONE"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE, TRACES OF STEEL & MELTED GLASS ALONG SIDE
STONE IS ON LINE & 1.4' WEST OF MID POINT BETWEEN CORNERS EAST & WEST
SET 1/2" X 18" REBAR & REMON CAP IN CAST IRON BOX 4" BELOW GRAVEL ROAD GRADE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" X 18" REBAR & REMON CAP IN CAST IRON BOX
- TAG IN N SIDE OF BRACE POLE S74W 65.72'
- TAG S SIDE POWER POLE N66W 77.15'
- TAG S SIDE 36" OAK N82E 72.02'
- TAG S SIDE POWER POL N55E 158.10'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W. REED

DATED: JULY 3, 2000

Surveyor's Michigan License No. 33985

