

FEB 02 2000

BRANCH COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

11-08-1999 15:11:55

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber 00004 Page 0014

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT 345  
OF 1990 AT A MEETING HELD ON  
Oct. 6, 1999

*E.R. Reed, Co. Rep.*  
E. R. REED

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
BUTLER TWP		
1. Public Land Survey	T <u>5</u> S R <u>5</u> W	<u>I-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___	_____
	T ___ R ___	_____
3. Miscellaneous	S ___	_____
	T ___ R ___	_____
Property in Sec.	S ___	_____
	T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, EDWARD W. REED, in a field survey on SEPTEMBER 28, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 26-27-34-35, BUTLER TWP.

A. Description of original monument and accessories and/or subsequent restoration:

1825: R. CLARK, JR. - CORNER SET  
1878: M. KNOWLES - SET STONE 14 AND STONES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 1/2" X 18" PIPE IN LINE WITH FENCES N & S. FOUND SMALL STONES AROUND PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE.

IN LINE WITH FENCE LINES NORTH & SOUTH  
DUE SOUTH 27.76' ROUND WOOD ANCHOR POST  
DUE NORTH 30.38' R.R. WOOD GATE POST  
N 75 E 73.2' CENTER OF 30" CHERRY  
S 4 W 30.3' CENTER OF 24" BUTTERNUT

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Edward W. Reed

Date SEPTEMBER 28, 1999

EDWARD W. REED

Surveyor's Michigan License No. 33985