

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

BRANCH COUNTY REMONUMENTATION CORNER STATE OF MICHIGAN
LAND CORNER RECORDATION CERTIFICATE Branch County
Filing Requirement of Act 74, Mich. P.A. 1970 Recorded

For corners in

BRANCH	Located In:	Corner Code #
(County)		
BUTLER TWP.		
1. Public Land Survey	T <u>5</u> S R <u>5</u> W	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

12-30-1996 14:10:52

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0101**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												


I, EDWARD W. REED, in a field survey on NOVEMBER 8, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 CORNER COMMON TO SECTIONS 11, 12, 13, & 14, T5S, R5W, BUTLER TWP., BRANCH COUNTY, MI
 1826: R. CLARK, DEP. SURVEYOR, CORNER SET
 1895: I.D. MINER, FOUND REDDISH BOLDER, BRICK & POTTERY SET BY A.R. DAY
 1935: E.L. MINER, COUNTY SURVEYOR, FOUND CORNER STONE BURIED. 2" BELOW SURFACE REPLACED BROKEN TILE & POTTERY WITH CUT 18" BICYCLE FORK & BRICK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND REMAINS OF OLD BICYCLE FORK & BROKEN BRICK
 SET 1/2" X 18" REBAR & REMONUMENTATION CAP IN CAST IRON BOX FLUSH WITH ROAD SURFACE

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON NOV. 13, 1996
E.R. Reed, Co. Rep.
E.R. REED



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1/2" x 18" REBAR WITH REMONUMENTATION CAP IN CAST IRON BOX
 N21W 32.6' TO CENTER OF 12" CHERRY
 S53W 46.8' TO CENTER OF 48" OAK
 N28E 28.3' TO SW CORNER OF TELEPHONE PEDESTAL
 N74E 103.7' TO FACE OF RAILROAD TIE ANCHOR POST

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed* Date NOVEMBER 8, 1996
 Surveyor's Michigan License No. 33985