

RECORDED
FEB 02 2000

BRANCH COUNTY REMONUMATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
Filing Requirement of Act 74, Mich. P.A. 1970 Branch County
Recorded

SECTION

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| <u>BRANCH COUNTY</u> | Located In: | Corner Code # |
| BUTLER TWP | | |
| 1. Public Land Survey | T <u>5 S</u> R <u>5 W</u> | <u>M-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ | _____ |
| | T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ | _____ |
| | T _____ R _____ | _____ |
| Property in Sec. | S _____ | _____ |
| | T _____ R _____ | _____ |

11-08-1999 15:12:27

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0017

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on SEPTEMBER 9, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SE CORNER SECTION 13 & NE CORNER SECTION 24, BUTLER

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: R. CLARK JR. - CORNER SET
- 1889: J.H. BENNETT - FOUND STONE, WITNESSED
- 1916: C.B. NORTON- FOUND STONE 1' BELOW SURFACE, WITNESSED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE & 1'X24' PINCHED PIPE SET A ANGLE UNDER STONE, ALL OLD WITNESS NOW GONE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON WITH REMON CAP INSIDE OF PINCHED PIPE (REMOVED STONE) SET C-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE.

| | | |
|---------------------------------|-----------|--------|
| IRON OF RONALD HARNER # 22436 | DUE NORTH | 33.12' |
| CENTER OF 3' SQ. CONC. POST | S46E | 40.92' |
| POWER POLE | S70E | 105.6' |
| TELEPHONE PED | N70E | 111.6' |
| 4" STEEL (ROUND) FEN. COR. POST | S45W | 50.5' |

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

EDWARD W. REED

Date SEPTEMBER 9, 1999

Surveyor's Michigan License No. 33985

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON OCT. 6, 1999.

E.R. Reed, Co. Rep.
E.R. REED

