

FEB 13 2001

BRANCH COUNTY REMONUMENTATION PROGRAM

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

12-15-2000 14:08:14

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

For corners in

BRANCH	Located In:	Corner Code ##
(County)	QUINCY TWP.	
1. Public Land Survey	T 6 S R 5 W	A-05
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Liber 00004 Page 0131  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims, \_\_\_\_\_

QUINCY TWP., T6S, R5W

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EDWARD R. REED, P.S. in a field survey on OCTOBER 25, 2000, 18X, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

SECTION CORNER COMMON TO SECTIONS 7 & 18, ON THE WEST LINE OF QUINCY TWP.:

1829 - G.L.O. FIELDNOTES OF ORANGE RISDON, D.S.: "WEST BETWEEN SEC'S 7 & 18...80.00 INTERSECT W BDRY 35 LKS N OF POST. SET POST COR SEC'S 7 & 18".

1878 - M. KNOWLES, CO. SURVEYOR: "FOUND STONE. SET STONE 24 AND BRICK".

1999 - L.C.R.C. 4/37 BY E.R. REED, COUNTY SURVEYOR: FOUND A C-I MONUMENT BOX WITH NOTHING IN IT; FURTHER, I HAD PREVIOUSLY OBSERVED SAME MONUMENT BOX WITH A CAPPED IRON ROD IN SAME. FRED CUTCHER, P.S. #24592 STATED THAT HE HAD FOUND THE BOX WITH A SQUARE IRON BAR IN SAME ON A PREVIOUS OCCASION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

AS DESCRIBED BY L.C.R.C. 4/37, I FOUND A 1/2" REBAR IRON IN THE MONUMENT BOX. PLACED A BRANCH COUNTY REMONUMENTATION CAP ON THE REBAR; AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

*E.R. Reed, P.S.*  
E.R. REED, Co. REP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENTATION CAP, ON REBAR, IN C-I MONUMENT BOX:

N 55 W 54.5' - CENTER OF 26" MAPLE.


S 30 W 52.10' - NE CORNER OF SQUARE CONCRETE POST.

SOUTH 24.5' - CORNER MONUMENT TO COLDWATER TWP., SECTIONS 12/13.

SOUTH 12.7' - CENTERLINE OF STATE ROAD PAVEMENT.

**NOTICE**  
THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAP-MAKING PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED OR SENT PUBLIC TO REGISTER OF DEEDS FOR COPIES.

Signed by *Edward R. Reed*  
EDWARD R. REED, P.S.  
Surveyor's Michigan License No. 7437



Date OCTOBER 25, 2000