

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #
QUINCY TWP.	T 6 S R 5 W	A-7
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
Branch County
Recorded

10-22-1997 09:57:21

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00003 Page 0170

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on APRIL 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: O. RISDON, DEP SURVEYOR, CORNER SET
- 1857: M. KNOWLES, CO. SURVEYOR, STONE & BRICK
- 1890: J.H. BENNETT, SURVEYOR, FOUND STONE & IRON WELL PRESERVED
- 1960: E.R. REED, COUNTY SURVEYOR, FOUND IRON & BRICK
- 1972: E.R. REED, COUNTY SURVEYOR, FOUND STONE & IRON SURROUNDED BY BRICK
RECORDED IN LCRC # 0031
- 1973: MILTON DEKEYSER, SURVEYOR, FOUND 3/4" IRON & BRICK,
RECORDED IN LCRC # 0080

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON ROD IN BRICK, RR SPIKE OVER TOP, SET 1/2"X9" REBAR & REMON CAP ON TOP OF 3/4" IRON, SET CI-MONUMENT BOX FLUSH WITH ROAD SURFACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

IRON ROD, REM CAP IN CI-MONUMENT BOX

- SQUARE WOOD ANCHOR POST, EAST 29.8
- SE CORNER STONE PORCH, S80W 52.0'
- POWER POLE, N18E 124.5'
- SE CORNER HOUSE, N25W 162.4'
- POWR POLE, EAST 30.8'
- SE CORNER HOUSE, S80W 62.8'
- 6" MAPLE, S40W 43.1'
- COLDWATER TWP. SECTION CORNER, SOUTH 95.72

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97

E.R. Reed, P.S. Co. Rep.
E.R. REED


AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed

Date APRIL 26, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1978

REVISED JAN., 198
REVISED OCT., 199