

RE
 FEB 17 2005
 SECTION

STATE OF MICHIGAN
 Branch County
 Recorded
 Filing Requirement of Act 74, Mich. P.A. 1970

11-08-1999 15:13:48

Linda Lee Morrison-Mathews
 REGISTER OF DEEDS

Liber 00004 Page 0026

Register of Deeds Stamp & File Number

For corners in

<u>BRANCH COUNTY</u> QUINCY TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>6 S</u> R <u>5 W</u>	<u>B-07</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, EDWARD W. REED, in a field survey on May 25, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Quarter Corner Common to Sections 18 & 19

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: ORANGE RISDON-CORNER SET
- 1887: M. KNOWLES. CO. SURVEYOR - STONE
- 1964: E.R. REED, CO SURVEYOR-FOUND IRON BAR, SET 1" DIAMETER PIPE & WITNESSES
- 1973: A.J. HATT - SURVEYOR - FOUND IRON PIPE - RECORDED IN LCRC, #062
- 1973: M. DEKEYSER, SURVEYOR - FOUND IRON PIPE RECORDED IN LCRC#0080
- 1990: E.W. REED, SURVEYOR - FOUND IRON IN MONUMENT BOX FITTING WITNESS OF LCRC#0080

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" DIAMETER PIPE IN MONUMENT BOX FITTING WITNESS OF LCRC# 062 & 080

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" x 18" REBAR & REMON CAP INSIDE OF 1" IRON PIPE SET IN CI- MONUMENT BOX

TOP CENTER OF WELL	S64E	147.14'
TOP CENTER OF TEL. PED.	N15E	125.72'
NAIL IN UTILITY POLE	N25E	139.50'
ADVENTIST SIGN POST, UPRIGHT	EAST	39.6'
CENTERLINE OF ROAD	WEST	7.4'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
 EDWARD W. REED

Date MAY 25, 1999

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7			8			9			10			12
5													
6	18			17			16			15			13
7													
8	19			20			21			22			24
9													
10	30			29			28			27			25
11													
12	31			32			33			34			36
13													

ACCEPTED BY THE BRANCH COUNTY SURVEYOR REED GROUP AS THE OFFICIAL SURVEY UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT MICHIGAN MEETING HELD ON Dec. 6, 1999
E.W. Reed Co. Rep.
 E.R. REED

