

**SURVEY & REMONUMENTATION**

MAR 13 1998

**SECTION**

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

10-22-1997 09:57:28

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber **00003** Page **0171**  
Register of Deeds Stamp & File Number

For corners in

BRANCH (County)	Located In:	Corner Code #
QUINCY TWP.		
1. Public Land Survey	T <u>6</u> S R <u>5</u> W	B-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on APRIL 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
QUARTER CORNER TO SECTION 31, QUINCY TWP

- 1825: J. MULLETT, DEPT SURVEYOR - CORNER SET  
OLD CORNER NOTES : STAKE
- 1986: E.R. REED, CO. SURVEYOR - UNABLE TO LOCATE OLD STAKE, RESET 1/2"  
X 18" REBAR FROM OLD WITNESS, RECORDED IN LCRC # II-0093
- 1995: E.W. REED, SET MONUMENT BOX DURING ROAD RECONSTRUCTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON ROD IN CI-MONUMENT BOX FITTING WITNESS OF #II-0093

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1/2" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX

- 12" SQUARE CONC. ANCHOR POST, WEST 21.7'
- 8.0' WEST OF N-S ROAD CENTERLINE
- 30" ASH, N302 34.0' TO CENTER
- POWER POLE, WEST 44.4'
- TEL. PED. N60E 55.2'
- 16" WALNUT, S34W 45.9' TO CENTER
- 16" WALNUT, S30W 50.2' TO CENTER

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97

*E.R. Reed, P.S. Co. Rep.*


**E.R. REED**

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed  
EDWARD W. REED

Date APRIL 29, 1997

Surveyor's Michigan License No. 33985



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28  
REVISED MAY 14, 1975

REVISED JAN, 198  
REVISED OCT, 199