

SURVEY & REMONUMENTATION

FEB 13 2001

SECTION

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

For corners in

BRANCH (County)	Located In:	Corner Code: #
	QUINCY TWP.	
1. Public Land Survey	T <u>6</u> S R <u>5</u> W	F-01
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

12-15-2000 14:08:23

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0132**
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims. _____

QUINCY TWP., T6S, R5W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EDWARD R. REED, in a field survey on NOVEMBER 8, 2000, 18x, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- NORTH 1/4 CORNER OF SECTION 4, T6S, R5W, QUINCY TWP.:
- 1825: FIELD NOTES OF JOHN MULLETT, D.S., AND WM. BROOKFIELD, D.S. G.L.O. REFERENCES TO THE NORTH LINE OF SECTION 4.
- 1958: UNRECORDED PLAT OF "HEN-BER HOMESITES", BY H. L. RUSSELL, RLS, REFERENCED TO SAID 1/4-CORNER.
- 1987: L.C.R.C. 11-102, BY E. R. REED, RLS, & COUNTY SURVEYOR. FOUND STONE, SET IRON STAKE OVER STONE, IN C-1 MONUMENT BOX.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A NEW ASPHALT PAVEMENT AND FILL HAS BEEN RECENTLY PLACED OVER THE MONUMENT BOX. I DUG AND FOUND THE C-1 MONUMENT BOX AT A DEPTH OF ABOUT 16" BELOW NEW ROAD PAVEMENT. ALSO FOUND THE IRON STAKE IN THE MONUMENT BOX.

PLACED A BRANCH COUNTY REMONUMENTATION CAP ON THE IRON STAKE, AND SET STAKE IN CONCRETE. SET A MONUMENT BOX AT ROAD SURFACE.

AND ACCEPTED THIS AS A CAREFUL AND FAITHFUL BEST EVIDENCE OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


BRANCH COUNTY REMONUMENTATION CAP ON IRON STAKE, SET IN CONCRETE, & IN A CAST-IRON MONUMENT BOX:

SOUTH 40 EAST 36.30' - SPOTTER, EAST SIDE OF ROUND WOOD POST (FENCELINE E-W).
 NORTH 43 WEST 48.72' - SPOTTER SW SIDE OF WOOD CORNER POST (FENCELINES N & E).
 NORTH 44 WEST 51.25' - SE CORNER OF TELEPHONE PEDESTAL.
 SOUTH 27.70' - TOP, CENTER OF TELEPHONE PEDESTAL.
 IN LINE WITH FENCELINE RUNNING SOUTH.
 2.7' SOUTH OF C/L E-W ROAD PAVEMENT.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E.R. Reed, P.S.
E.R. REED, C.S. REP.

Signed by Edward R. Reed
EDWARD R. REED, P.S.



Date NOVEMBER 8, 2000

Surveyor's Michigan License No. 7437

NOTICE
THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED AND PUBLIC TO REGISTER OF DEEDS FOR COPIES

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983