

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH</u>	Located In:	Corner Code #
(County)		
QUINCY TWP.	<u>T 6 S R 5 W</u>	<u>F-11</u>
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
Branch County
Recorded

10-22-1997 09:57:56

Linda Lee Morrison-Mathews
REGISTERED DEEDS
Liber **00003** Page **0175**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on SEPTEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
9-10-97

E.R. Reed, P.S. Co. Rep.
E.R. REED

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: WM BROOKFIELD, DEPT. SURVEYOR - CORNER SET
- 1923: E.L. MINER, CO. SURVEYOR - UNABLE TO LOCATE POST, RESET CORNER ON LINE AT 2640 WEST OF SECTION CORNER, SET A FORD DRIVE SHAFT SURROUNDED BY SMALL STONES.
- 1927: E.L. MINER TIED PLAT OF "CEDAR POINT SUBDIVISION" TO CORNER
- 1957: E.R. REED TIED PLAT OF "SILVER DOLLAR CIRCLE" TO CORNER
- E.R. REED TIED PLAT OF "BOWERMAN'S LANDING" TO CORNER
- 1976: E.R. REED, CO. SURVEYOR - FORD AXLE SHAFT OBLITERATED BY ROAD CONSTRUCTION, RESET 3/4" IRON BY RETRACING SURVEY OF MINER'S 1923 SURVEY. RECORDED IN LCRC # 184

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" SOLID IRON ROD AS DESCRIBED IN LCRC # 184

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD SURFACE

- TAG ON N. SIDE 36" MAPLE, S6E 27.55'
- NAIL & WASHER E. SIDE 8" MAPLE, N50W 46.45'
- NAIL & WASHER N. SIDE 14" TWIN WALNUT, S81W 83.71'
- NAIL & WASHER S. SIDE 6" MAPLE, N45E 31.81'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*

Date SEPTEMBER 3, 1997

EDWARD W. REED
Surveyor's Michigan License No. 33985

