

SURVEY & REMONUMENTATION

FEB 08 1999

SECTION

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH COUNTY</u> QUINCY TWP	Located in:	Corner Code #
1. Public Land Survey	T <u>6 S</u> R <u>5 W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

12-07-1998 13:54:07

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0253**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

11-01-1998

E.R. Reed Co. Rep.
E.R. REED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTH QUARTER CORNER, SECTION 33, QUINCY TWP

A. Description of original monument and accessories and/or subsequent restoration:

1825: JOHN MULLET, DEPT. SURVEYOR - CORNER SET
1953: E.R. REED, CO SURVEYOR - FOUND STONE
3/63 PLATS - PLAT OF "HIGH BANK" TIED TO CORNER
6/36 PLATS - PLAT OF "MAPLE HAVEN NO. 2" TIED TO CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD IN CI-MONUMENT BOX SET BY MYSELF FOR COUNTY 299 FUND PROJECT
FITTING WITNESS OF E.R. REED, CO SURVEYOR

SET REMON CAP OVER IRON, AND RAISED TO NEW PAVEMENT ROAD SURFACE WITH EXTENSION RINGS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX

IN LINE WITH FENCE RUNNING NORTH

4 TRUNK ELM S42E 28.3' TO CENTER TRUNK
POWER POLE S47W 61.2' TO FACE
TEL PED S65W 53.9' TO FACE
8" ELM N45W 37.1' TO CENTER
SE COR. GARAGE N20W 102.1'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W, REED

Date NOV. 4, 1998

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

