

SURVEY & REMONUMENTATION

BRANCH COUNTY REMONUMENTATION PROGRAM

FEB 13 2001

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 Branch County
 Recorded

SECTION

For corners in

<u>BRANCH COUNTY</u> QUINCY TWP	Located In:	Corner Code #
1. Public Land Survey	<u>T 6 S R 5 W</u>	<u>G-12</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims <u> </u>		

12-15-2000 14:08:38

Linda Lee Morrison-Mathews
 REGISTER OF DEEDS

Liber **00004** Page **0133**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E. R. Reed, P.S.
 E. R. REED, Co. Rep.

I, EDWARD W. REED, in a field survey on OCT. 10, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 33 & 34; QUINCY TWP., BRANCH COUNTY, MI

A. Description of original monument and accessories and/or subsequent restoration:

1825: ORANGE RISDON-CORNER SET
 1998: JOHN E. MAXSON, P.S.-SURVEY TIED TO CORNER-NO WITNESS OR LCRC RECORDED, NO EVIDENCE OF CORNER
 1999: JOHN E. MAXSON, P.S.-SURVEY-BOTH 1998 & 1999 SURVEYS BY MAXSON MAKE REFERENCE AS BEGINNING AT THE 1/4 CORNER BUT THERE ARE NO WITNESSES TO OR INDICATION OF THE NATURE OF THE 1/4 CORNER; AND NO. LCRC'S HAVE BEEN RECORDED BY MAXSON FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER-ORIGINAL CORNER NOW GONE DUE TO MAJOR ROAD REBUILDING BY COUNTY HIGHWAY DEPARTMENT
 SET POINT ON LINE & MIDWAY BETWEEN RECORDED CORNERS NORTH & SOUTH
 SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE
 TAG EAST SIDE OF POWER POLE N44W 73.0'
 SOUTH END OF ROAD CULVERT S72E 41.3'
 TELEPHONE PEDESTAL S21E 58.5'
 CENTERLINE NORTH-SOUTH ROAD EAST 6.0'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
 EDWARD W. REED

Surveyor's Michigan License No. 33985



NOTICE
 THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAP PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED SEND PUBLIC TO REGISTER OF DEEDS FOR COPIES

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995