

RECORDED

FEB 17 2000

BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
Branch County
Recorded

12-30-1999 11:02:26

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0060

SECTION

For corners in

<u>BRANCH COUNTY</u> QUINCY TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>6 S</u> R <u>5 W</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
DEC. 07, 1999

E.R. Reed, P.S.
E. R. REED

I, EDWARD W. REED, in a field survey on OCT. 21, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NORTH QUARTER CORNER SECTION 2, QUINCY TWP.

A. Description of original monument and accessories and/or subsequent restoration:

1825: JOHN MULLET-CORNER SET
1878: M. KNOWLES-SURVEY TO SET CORNER
OLD SURVEY NOTES INDICATE "STONE"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

TAKING FENCE AND OCCUPATIONS LINES EAST AND WEST, DUG HOLE & FOUND POINTED STONE SET 1/2" X 18" REBAR WITH REMON CAP IN CAST IRON MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR WITH REMON CAP IN CAST IRON MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE
NE CORNER FAP MARKER S39W 48.00'
NE CORNER TELEPHONE PEDESTAL S62W 61.60'
ROUND WOOD ANCHOR POST S30E 51.6'
CENTER 42" MAPLE N4W 42.2'
CENTER OF 6" PINE N68W 94.0'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

EDWARD W. REED

Date OCT 20, 1999

Surveyor's Michigan License No. 33985

