

SURVEY & REMONUMENTATION

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-16-94

APR 26 1995
BRANCH COUNTY REMONUMENTATION CORNER
STATE OF MICHIGAN
LAND CORNER RECORDATION CERTIFICATE
Branch County
Filing Requirement of Act 74, Mich. P.A. 1970
Recorded

E. R. Reed Co. Rep.

For corners in

BRANCH <small>(County)</small>	Located In:	Corner Code	
COLDWATER TWP.		A - 5	
1. Public Land Survey	T <u>6</u> S R <u>6</u> W		
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

12-28-1994 15:03:36

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00002** Page **0309**
Register of Deeds Stamp & File Number

I, EDWARD R. REED in a field survey on NOVEMBER 30 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5: NORTHWEST CORNER OF SECTION 18, COLDWATER TWP., T6S, R6W.

G.L.O. FIELDNOTES, W. BROOKFIELD, 1825: "T6S, R6W, WEST ON RANDOM BETWEEN SEC'S 7 & 18 79.95 INTERSECT W BOUNDARY 35 LKS S OF COR POST".

MI. DEPT. STATE HIGHWAYS SECTION CORNER FILE CARD: G.E. ANDERSON, SURVEY CHIEF, 9-15-70- "SECTION COR COMMON TO SECTIONS 7 & 18 OF T6S R6W COLDWATER TWP & T6S R7W BATAVIA TWP SECTIONS 12 & 13. FD. LARGE STONE (12"x10"x8") 1' BELOW SURFACE WITH RED BRICK AROUND IT. 1' SOUTH OF FE. LINE WEST & 5½' WEST OF C/L HODUNK RD. C/L HURLEY RD EAST. PLACED ¾"x32" BLACK PIPE IN MON. BOX IN PLACE OF STONE: SET STONE UNDER MON. BOX". (WITNESSES)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A. (CONTINUED):

L.C.R.C. # II-104, 1987 - E. R. REED, CO. SURVEYOR: FOUND ¾" IRONPIPE FROM MSHD WITNESSES.


E. R. REED, CO. SURVEYOR - TWO SURVEYS IN SEC. 18, T6S, R6W, REFERNCED TO THIS CORNER.

B. FOUND ¾" IRON PIPE IN MON. BOX, TOP OF BOX IS NOW 18" BELOW BLACKTOP ROAD PAVEMENT. REMOVED MON. BOX COVER; SET ½" STEEL REBAR ROD IN IRON PIPE WITH #7437 CAP ON ROD; SET ½"x14" STEEL REBAR ROD WITH BRANCH COUNTY REMONUMENTATION CAP, ON TOP OF PIPE, IN NEW C-I MONUMENT BOX AT ROAD PAVEMENT. AND ACCEPTED THIS AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1/2" STEEL REBAR ROD, WITH BRANCH COUNTY REMONUMENTATION CAP, OVER PIPE OVER STONE, IN C-I MONUMENT BOX.

S 22 E 73.54' 18" HICKORY. S 70 E 95.96' 22" TWIN HICKORY.
S 40 E 46.85' TO CENTER SQ. TEL. PEDESTAL.
N 25 W 51.18' TO NEAR FACE OF TSFR. POWER POLE.
WEST 32.20' TO NE COR RECTANGULAR TEL. PEDESTAL.
2' EAST OF C/L N-S BLACKTOP ROAD
AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward R. Reed*
Surveyor's Michigan License No. 7437
EDWARD R. REED



Date NOVEMBER 30, 1994