

SURVEY & REMONUMENTATION

APR 26 1995

BRANCH COUNTY REMONUMENTATION CORNER
LAND COMMISSION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
12-16-94

E. Reed Co. Rep.

For corners in

Branch <small>(County)</small>	Located In:	Corner Code --#
1. Public Land Survey	T <u>6</u> S R <u>6</u> W	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

12-28-1994 15:05:16

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number
Liber 10002 Page 0019

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward W. Reed, in a field survey on September 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Corner common to Sections 20, 21, 28 and 29, Town 6 South, Range 6 West, Coldwater Township, Branch County, Michigan.
- 1829: GLO notes, corner set
- 1874: Knowles, found stake; planted stone and cobbles
- 1907: Hamilton, found stone
- 1939: Terrill found corner- iron rod, 2 x 2 wood stake, stone and brick
- 1967: E. R. Reed, found corner
- 1972: E. R. Reed, 3/4" iron rod over stone and broken bricks, recorded #36
- 1981: E. R. Reed, iron rod in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 3/4" x 18" iron rod in cast iron box
- Removed rod and set 1/2" x 18" iron rebar with remonumentation cap
- Cast iron box left as set



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" rebar as noted above:
- North 5 East 29.2-to face of power pole
- South 31 East 58.80-to face of power pole
- North 75° East 96.35-to face of power pole
- North 58 West 74.11-to face of power pole
- South 58 West 167.22-northeast corner of fence for Coldwater Board of Public Utilities high voltage substation

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date September 7, 1994
Surveyor's Michigan License No. 33985