

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

BRANCH COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN Branch County Recorded

10-22-1997 09:54:55

Linda Lee Morrison-Mathews REGISTER OF DEEDS

Liber 00003 Page 0150

Register of Deeds Stamp & File Number

For corners in

Form with fields for BRANCH (COLDWATER TWP.), Located In (T 6 S R 6 W), Corner Code # (E-13), and numbered items 1-5.

I, EDWARD W. REED, in a field survey on JULY 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: SOUTHEAST CORNER SECTION 32, SOUTHWEST CORNER SECTION 33 COLDWATER TOWNSHIP

- 1825: WM. BROOKFIELD, DEPT. SURVEYOR - SET CORNER
1971: E.R. REED, CO. SURVEYOR - FOUND STONE 16" DEEP SURROUNDED BY SMALL STONES, SET 3/8" IRON ROD ON TOP OF STONE, RECORDED IN LCRC # 0018
1992: E.R. REED, CO. SURVEYOR - SET CI-MONUMENT BOX DURING ROAD REPAVING PROJECT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MONUMENT BOX WITH 1/2" X 18" REBAR IRON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET REMON CAP ON IRON ROD, RAISED CI-MONUMENT BOX 1 1/2" WITH RINGS TO ROAD SURFACE

- WOOD GATE AND ANCHOR POST, DUE NORTH 30.4' TO NEAR FACE
L-IRON ANCHOR POST, S58W 50.7'
POWER POLE, S16E 64.8' TO NEAR FACE
CENTER, EAST END OF E-W CORR. METAL PIPE ROAD CULVERT, S45W 31.2'
CENTER, WEST END E-W CORR. METAL PIPE ROAD CULVERT, S61W 42.4'
POWER POLE, N66E 65.5' TO NEAR FACE
CENTERLINE OF ROAD SOUTH, WEST 6.8'
IN CENTERLINE OF EAST AND WEST ROAD.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97

E.R. REED, Co. Rep. E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by [Signature] Date JULY 19, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985

