

1993

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

BRANCH (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6S</u> R <u>6W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

251

REGISTER OF DEEDS

John J. Morrison

93 DEC 27 AM 10:06

REC'D FOR RECORD
STATE OF MICHIGAN
BRANCH COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward W. Reed in a field survey on November 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
NORTH SECTION CORNER COMMON TO SECTIONS 3/4, COLDWATER TOWNSHIP, T6S, R6W

1829: W. Brookfield, GLO Dep. Surveyor. Set post corner section 3/4, Beech 14" S 3; Beech 12" S 76 W 29.

1882: Knowles, Surveyor, Found stake and stones.

1963: E. R. Reed, County Surveyor: Section Corner is 37 lks (24.42') west of SE corner Section 33, T5S, R6W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Witness now gone, except SE corner Section 33, measured 24.42 feet west of said Girard corner and found P.K. and flagging under 4" asphalt mat and 3" concrete, marked point and dug under 3" more concrete to old fill dirt, unable to locate stake or stones.


Set 1/2" x 18" rebar iron with I.D. cap in CI monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Rebar iron stake as noted above.
- N 40 W 58.3' - Power Pole
- S 57 W 54.5' - Power Pole
- East 9.1' - C/L N-S road
- S 45 E 75.1" - Power Pole

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *Edward W. Reed*
Surveyor's Michigan License No. 33985



Date November 9, 1993