

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

BRANCH COUNTY REMONUMENTATION CORNER STATE OF MICHIGAN
 LAND CORNER RECORDATION CERTIFICATE Branch County
 Filing Requirement of Act 74, Mich. P.A. 1970 Recorded

For corners in

BRANCH (County) COLDWATER TWP.	Located in:	Corner Code #
1. Public Land Survey	T <u>6S</u> R <u>6W</u>	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

12-30-1996 14:10:30

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00003 Page 0098

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, EDWARD W. REED, in a field survey on NOVEMBER 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: O. RISDON, DEP. SURVEYOR, CORNER SET
- 1866: A.R.DAY, CO. SURVEYOR, GRAY HARD STONE 2 FEET LONG SET IN GROUND WITH BRICKS BURIED AROUND
- 1928: F. SOLL, SURVEYOR, SURVEY OF STATE PUBLIC SCHOOL, "CORNER FOUND"
- 1947: H. RUSSELL, CO. SURVEYOR, CORNER FOUND
- 1973: A.J. HATT, SURVEYOR, "IRON IN MONUMENT BOX" RECORDED L.C.R.C.#068


CORNER COMMON TO SECTIONS 3, 4, 9 & 10, T6S, R6W, COLDWATER TWP., BRANCH COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND AXLE SHAFT & BEVEL GEAR IN MONUMENT BOX, UNABLE TO REMOVE
 DROVE AXLE 6" BELOW, CONCRETED REMONUMENTATION CAP OVER TOP OF AXLE

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON Nov. 13, 1996

E.R. Reed, Co. Rep.
E.R. REED



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- AXLE WITH REMONUMENTATION CAP IN CAST IRON BOX
- S42E 88.28' TO NAIL SW SIDE 20" APPLE
- N86W 69.74' TO NAIL AND WASHER ON NORTH SIDE OF POWER POLE
- S58E 43.42' TO NAIL & WASHER ON SOUTH SIDE OF POWER POLE
- CENTERLINE ROAD EAST 4.20'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed Date NOVEMBER 4, 1996
 Surveyor's Michigan License No. EDWARD W. REED 33985