

**SURVEY & REMONUMENTATION**

MAR 21 1997

COMMISSION

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #
COLDWATER TWP.	T <u>6 S R</u> <u>6 W</u>	<u>G-11</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

00003 Page 0067  
STATE OF MICHIGAN

Branch County  
Recorded  
10-30-1996 09:18:42

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Edward W. Reed, in a field survey on JULY 5, 19 '96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- CORNER COMMON TO SECTIONS 27, 28, 33 & 34, COLDWATER TWP., T6S, R6W, BRANCH COUNTY, MI
- 1829: O. RISDON, DEP. SURVEYOR, CORNER SET
- 1909: J. COX, COUNTY SURVEYOR, FOUND SECTION CORNER, ROUND IRON 4" DIAMETER IN DEPOSIT OF CROCKERY & STONE, "I DO NOT KNOW WHO SET IT-UNRECORDED"
- 1974: D. PEIRCE, RLS, FIELD NOTES INDICATE FOUND 3" BUGGYSHAFT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 3 1/2" BUGGY AXLE & CROCKERY
- SET 1/2" x 18" IRON INSIDE AXLE & REMONUMENTATION CAP
- SET CAST IRON REMONUMENTATION BOX OVER SAME



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1.5' E & 1.0" S OF ANGLE IRON CORNER POST
- N 41.0' TO CENTER OF 6" APPLE
- W 32.7' TO CENTER OF 12" ELM
- S80E 91.0' TO CENTER OF 14" DOUBLE WALNUT
- W 4.0' TO CENTER OF 6" TRIPLE ELM
- 1/2" X 18" IRON WITH REMONUMENTATION CAP IN CAST IRON BOX

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Oct 9, 1996

E.R. Reed Co. R.P.  
E.R. REED

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date JULY 5, 1996  
Surveyor's Michigan License No. 33985