

# SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber **00003** Page **0068**

For corners in

<u>BRANCH</u> <small>(County)</small>	Located In:	Corner Code -#	
<u>COLDWATER TWP.</u>			
1. Public Land Survey	T <u>6 S</u> R <u>6 W</u>	<u>H-5</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN  
Branch County  
Recorded  
  
10-30-1996 09:18:55  
  
Linda Lee Morrison-Mathews  
REGISTER OF DEEDS  
  
**Register of Deeds Stamp & File Number**

I, Edward W. Reed, in a field survey on AUGUST 12, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5					●								
6		16	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration: QUARTER CORNER COMMON TO SECTIONS 14 & 15, T6S, R6W, COLDWATER TWP.  
 1829: O. RISDON, DEP. SURVEYOR, CORNER SET  
 1928: F. SOLL, STATE SURVEYOR, FOUND STONE ON END WITH BRICK AT ITS NORTH SIDE, POINTED STONE AND BRICK IDENTIFIED IN PREVIOUS RESURVEY FROM ORIGINAL GOVERNMENT SURVEY, SET STANDARD MI MONUMENT  
 1979: E.R. REED, COUNTY SURVEYOR, FOUND IRON BAR  
 1985: D. BEVER, M.S.H.D. SURVEYOR, FOUND RR SPIKE OVER REMAINS OF OLD S.M.M., SET 3/4" PIPE IN CAST IRON BOX, RECORDED L.C.R. #II-0077

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 3/4" PIPE & CAP IN CAST IRON BOX  
 REMOVED PIPE AND SET 1/2" X 12" REBAR IRON AND REMONUMENTATION CAP

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

Oct. 9, 1996  
*E.R. Reed, Co. Rep.*  
**E.R. REED**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" x 12" REBAR WITH REMONUMENTATION CAP IN CAST IRON BOX  
 N45E 92.83' TO CHISELED "+" IN S BASE STEEL LIGHT POLE  
 N65W 137.00' TO CHISELED "+" IN S BASE STEEL LIGHT POLE  
 S75W 240.45' TO NE CORNER MICHIGAN STATE POLICE BLOCK BUILDING  
 N89 degrees 56' 30" E 2669.63' TO SE CORNER SECTION 10, T6S, R6W  
 S68E 98.7' TO NAIL & TAG 2' UP WEST SIDE OF POWER POLE  
 S05E 45.1' TO FACE OF TELEPHONE PEDESTAL  
 S82W 106.7' TO FACE OF TELEPHONE PEDESTAL



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *Edward W. Reed* Date AUGUST 12, 1996  
 Surveyor's Michigan License No. 33985