

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

BRANCH COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN Filing Requirement of Act 74, Mich. P.A. 1970 Branch County Recorded

For corners in

BRANCH Located In: Corner Code # COLDWATER TWP. 1. Public Land Survey T 6 S R 6 W 1-7 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R

10-22-1997 09:55:03

Linda Lee Morrison-Mathews REGISTER OF DEEDS

Liber 00003 Page 0151

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, EDWARD W. REED, in a field survey on SEPT. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1829: O. RISDON, DEPT. SURVEYOR - SET CORNER 1876: J.H. BENNETT, COUNTY SURVEYOR - FOUND STAKE, SET 3 BRICKS 1883: M. KNOWLES, DEPT CO. SURVEYOR - FOUND STONE 1945: H.L. RUSSELL, CO. SURVEYOR - STANDARD 4"X4"X4' CONC. MONUMENT 1975: D. BOONE, SURVEYOR - FOUND 3/8" IRON PIN & CASTING, RECORDED IN LCRC # 0137

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner FOUND CONC. MONUMENT IN SQUARE MONUMENT BOX AS DESCRIBED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET REMON CAP ON IRON FROM CONCRETE MONUMENT IN SQUARE MONUMENT BOX

NAIL & CAP 2' UP N. SIDE 30" MAPLE, N89W 28.60' SW CORNER 2' SQUARE CONCRETE ANCHOR POST, EAST 30.21' NAIL & WASHER W. SIDE POWER POLE, N30E 74.00' NAIL & WASHER W. SIDE POWER POLE, EAST 30.71' NAIL & WASHER W. SIDE POWER POLE, S15E 89.28' NAIL & WASHER E. SIDE TEL. POLE, WEST 19.85' CENTER OF MANHOLE COVER, SOUTH 25.4'

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97

E.R. Reed, P.S. & C. Rep. E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed Date SEPTEMBER 3, 1997

EDWARD W. REED Surveyor's Michigan License No. 33985

