

**SURVEY &  
REMONUMENTATION**

**MAR 13 1998**

**SECTION**

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
Branch County  
Recorded

For corners in

10-22-1997 09:55:10

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

<u>BRANCH</u> (County)	Located In:	Corner Code #
COLDWATER TWP.	T 6 S R 6 W	I-12
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Liber 00003 Page 0152

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on APRIL 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
QUARTER CORNER COMMON TO SECTIONS 34 & 35

1829: O. RISDON, DEPT. SURVEYOR - SET CORNER  
1874: BENNETT, COUNTY SURVEYOR - FOUND STONE

ACCEPTED BY THE BRANCH COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT 345  
OF 1990 AT A MEETING HELD ON

9-10-97  
*E. R. Reed, P.S. Co. Rep.*  
**E.R. REED**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX WITH STONE UNDER - MONUMENT BOX SET BY COUNTY ROAD COMMISSION DURING ROAD RECONSTRUCTION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET 1/2"X18" REBAR IRON, REMON CAP IN CI-MONUMENT BOX

STEEL CORNER POST, N84W 32.55 TO FACE  
WOOD POST, S80E 33.7 TO FACE  
12" MAPLE, S34W 91.65 TO NAIL AT CENTER  
TEL POLE, S12E 120.0 TO NEAR FACE

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*  
EDWARD W. REED

Date APRIL 29, 1997

Surveyor's Michigan License No. 33985

