

# SURVEY & REMONUMENTATION

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-16-94

APR 26 1995

BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
COMMISSION  
Filing Requirement of Act 74, Mich. P.A. 1970

E. Reed, Co. Rep.

For corners in

<u>Branch</u> <small>(County)</small>	Located In:	Corner Code <u>==</u>	
1. Public Land Survey	T <u>6</u> S R <u>6</u> W	<u>J-11</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN  
Branch County  
Recorded

12-28-1994 15:05:49

Libar 00002 Page 0323  
Linda Lee Holtson-Matthews  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Edward W. Reed, in a field survey on September 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11									●				
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 Quarter corner common to Sections 26 and 35, Town 6 South, Range 6 West, Coldwater Township, Branch County, Michigan  
 1829: Brookfield, set 1/4 corner  
 1860: Knowles, stone  
 1880: Knowles, found stone and brick  
 1963: M.S.H.D., found pointed stone  
 1974: E. R. Reed, iron pipe over stone in cast iron box  
 1993: E. W. Reed, found iron rod over stone in cast iron box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1/2" pipe in cast iron monument box  
 Removed pipe  
 Set 1/2" x 18" rebar iron and remonumentation cap  
 Set ring to raise to road surface

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 1/2" rebar as noted above:  
 North 30 West 51.75-corner centerline iron post  
 North 60 East 53.3-corner post  
 Due East 8.3-centerline of road North  
 South 27 West 37.15-nail on East side 24" maple  
 North 25 West 50.13-telephone pedestal



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date September 12, 1994  
 Surveyor's Michigan License No. 33985