

1993

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
BRANCH

(County)	Located In:	Corner Code #/7
1. Public Land Survey	T <u>6S</u> R <u>6W</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REC'D FOR RECORD
STATE OF MICHIGAN
BRANCH COUNTY

93 DEC 27 AM 10:07

REGISTER OF DEEDS

258

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward W. Reed in a field survey on November 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NE CORNER SECTION 2, NW CORNER SECTION 1, T6S, R6W

1825: W. Brookfield, GLO Dept. Surveyor, set post cor sec 1 & 2 (all witness now gone)

1963: Max Stalter, Survey chief, MSHD; 3/4" iron pipe (all witness now gone)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dug hole down through 2 foot of new fill dirt to old pavement, 4" below old pavement found 3/4" iron pipe as described by MSHD notes.

Set 1/2" x 18" rebar iron with ID cap in CI monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Rebar iron as noted above.
- N 25 E 50.0', near face telephone pedestal
- N 75 E 95.3', near face telephone pedestal
- Due east 60.6', C/L road
- S 65 E 96.1, near face telephone pedestal
- N 10 W 70.0', near face power pole
- S 48 W 40.3', west end field drive culvert



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date November 24, 1993
Surveyor's Michigan License No. 33985