

1993

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

BRANCH (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6S</u> R <u>6W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

261

REC'D FOR RECORD
STATE OF MICHIGAN
BRANCH COUNTY
93 DEC 27 AM 10:07
John A. Morrison
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Edward W. Reed, in a field survey on November 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

SOUTHEAST CORNER OF SECTION 35, T6S, R6W, COLDWATER TWP.

1877: M. Knowles, Surveyor - set stone

1978: E.R. Reed, County Surveyor - found pointed stone, 1 1/4" iron pipe over stone, broken glass, orange flagging. Corner appears to have been recently recovered and used by David Boone, RLS # 18803 (not recorded by Boone), Reed recorded corner in Land Corner Records #00231

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4" iron pipe over stone as described by E.R. Reed in Land Corner Record # 00231.

Set 1/2" x 18" rebar iron with ID cap in CI-monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Rebar iron as noted above.

N 18 W 55.3', center of 12" Walnut

N 72 W 92.5', center of 14" Walnut

S 64 E 42.3', center of telephone pedestal

East 15.8', C/L of north-south road.



And is accepted as a careful and faithful perpetuation

of the position of the original corner. Signed by Edward W. Reed Date November 30, 1993

Surveyor's Michigan License No. 33985