

**SURVEY & REMONUMENTATION** BRANCH COUNTY REMONUMENTATION PROGRAM

FEB 13 2001

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

12-15-2000 14:08:49

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

For corners in  
BRANCH SECTION  
(County)

Located In:  
COLDWATER TWP.

Corner Code #

1. Public Land Survey

T 6 S R 6 W

M-05

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number  
00004 0134

COLDWATER TWP., T6S, R6W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EDWARD R. REED, P.S. in a field survey on OCTOBER 25, 2000 ~~XIX~~ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
SECTION CORNER TO SECTIONS 12 & 13 ON EAST TOWNSHIP LINE:

- 1825 - G.L.O. FIELDNOTES OF JOHN MALLETT, D.S.: "NORTH ON EAST BDRY OF SEC. 13.... 80.00 SET POST CORNER SEC. 12 & 13".
- 1858 - M. KNOWLES, COUNTY SURVEYOR: "LARGE STONE & EARTHEN".
- 1882 - M. KNOWLES, DEP. COUNTY SURVEYOR: "FOUND STONE".
- 1993 - EDWARD R. REED, RLS, COUNTY SURVEYOR: "FOUND BRICK & CAST IRON AT 27" DEPTH, BUT NO STONE." L.C.R.C. #1/275.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

AS PER L.C.R.C. 1/275, IN 1993, I HAD SEARCHED AN AREA 4'x4' TO A DEPTH OF THREE FT., AND FOUND ONE-HALF PIECE OF OLD BRICK 22" DEEP AND PIECE OF IRON CASTING AT 27" DEEP, BUT NO STONE; AND SET A STEEL REBAR IN C-1 MONUMENT BOX AT THIS LOCATION. FOUND THE STEEL REBAR IN C-1 MONUMENT BOX AS PREVIOUSLY NOTED; AND PLACED A BRANCH COUNTY REMONUMENTATION CAP ON SAID REBAR; AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1940 AT A MEETING HELD ON 11-28-2000

*E.R. Reed, P.S.*  
E. R. REED, C. REP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- BRANCH COUNTY REMONUMENTATION CAP ON STEEL REBAR, IN C-1 MONUMENT BOX:
- S 65 W 32.00' - NE CORNER OF 12" SQUARE CONCRETE ANCHOR POST.
- S 25 E 60.50' - TOP, CENTER OF ROUND CABLE PEDESTAL.
- N 30 W 69.20' - SPOTTER, SW SIDE OF 24" MAPLE.
- 16.4' SOUTH OF THE C/L OF E-W ROAD & 5' WEST OF C/L N-S ROAD.
- NORTH 24.5' - CORNER MONUMENT TO SEC'S. 7 & 18, QUINCY TWP., T6S, R5W.
- S 75 W 90.7' - TELEPHONE PEDESTAL.

Liber 00004 Page 0134

Signed by *Edward R. Reed*  
EDWARD R. REED, P.S.  
Surveyor's Michigan License No. 7437



Date OCTOBER 25, 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL RECORDING PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED OR SENT PUBLIC TO REGISTER OF DEEDS FOR COPIES.