

**BRANCH COUNTY REMONUMENTATION PROGRAM STATE OF MICHIGAN**  
**LAND CORNER RECORDATION CERTIFICATE** Branch County  
**Filing Requirement of Act 74, Mich. P.A. 1970** Recorded

For corners in SECTION

<u>BRANCH</u> (County)	Located In:	Corner Code #
<u>BATAVIA TOWNSHIP</u>		
1. Public Land Survey	T <u>6</u> S R <u>7</u> W	<u>A-08</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

12-30-1999 11:02:40

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber **00004** Page **0062**

Register of Deeds Stamp & File Number

I, EDWARD R. REED, P.S. field survey on DECEMBER 2, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

BATAVIA TWP.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: G.L.O. FIELDNOTES OF JOHN MULLET, D.S.: 40.00 SET QTR SEC POST.
- 1969: G. E. ANDERSON, MSHD: "FOUND FLAT BOTTOMED STONE BASE 17"x14"x10" HIGH, 4"x4" ON TOP ALSO FOUND SEVERAL SMALL STONES AROUND LARGE STONE. PLACED 3/4"x32" GALVANIZED PIPE IN MON. BOX WHERE STONE HAD BEEN. PLACED STONE AGAINST PIPE. STONE WAS FOUND 4" BELOW GRAVEL 4' E. OF W. EDGE OF EX. GRAVEL RD. (FOUR WITNESSES TO CORNER BY ANDERSON)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


USING EXISTING WITNESSES OF ANDERSON WHICH REMAIN, DUG AND FOUND PIPE IN MONUMENT BOX, ABOUT 12" BELOW ROAD SURFACE.  
 SET BRANCH COUNTY REMONUMENTATION CAP ON 1/2"x18" REBAR AND CEMENTED SAME IN PIPE. ALL IN C-I MONUMENT BOX, WHICH IS ABOUT 5 FEET WEST OF CENTERLINE OF N-S GRAVEL ROAD.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-07-99

E.R. Reed, P.S.  
E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENTATION CAP ON REBAR ROD IN PIPE, ALL IN C-I MONUMENT BOX:  
 N 22 E 104.43' - 48" MAPLE.  
 N 50 W 19.06' - 30" TRIPLE MAPLE.  
 N 90 E 47.0' - 48" MAPLE  
 S 18 W 43.2' - 30" TRIPLE MAPLE.  
 5' M/L WEST OF C/L GRAVEL ROAD.  
 164' NORTH OF E½ CORNER OF SECTION 24, T6S, R8W.



Signed by Edward R. Reed Date DECEMBER 2, 1999  
 EDWARD R. REED, P.S.  
 Surveyor's Michigan License No. 7437