

**SURVEY & REMONUMENTATION**

**FEB 13 2001**

**SECTION**

**BRANCH COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
Branch County  
Recorded

09-26-2000 10:17:47

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber **00004** Page **0103**

Register of Deeds Stamp & File Number

For corners in  
**BRANCH**  
(County)  
**MATTESON TWP.**

1. Public Land Survey	T <u>6</u> S R <u>8</u> W	<u>1 - 05</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

MATTESON TWP., T6S, R8W

I, **EDWARD R. REED, P.S.** in a field survey on APRIL 25, ~~XXX~~ 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826: G.L.O. FIELDNOTES OF WM. BROOKFIELD, D.S.: "SET POST, COR. SEC'S 10, 11, 14 & 15".
  - 1891: SURVEY BY IANTHIS D. MINER, COUNTY SURVEYOR: "CORNER TO SECS 10, 11, 14 & 15. FOUND STONE & IRON".
  - 1969: G.E. ANDERSON, MSHD: "FOUND 1" IRON PIPE IN LINE WITH FENCE TO NORTH. 2" BELOW GRAVEL SURFACE." WIT: S05W 46.93' 15" WALNUT, S65W 33.98' 12" WALNUT, N10E 27.76' 20" WALNUT."


- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FD THE 1" PIPE NOTED BY ANDERSON, FROM HIS WITNESSES.  
REMOVED PIPE AND REPLACED WITH A BRANCH COUNTY REMONUMENTATION CAP ON A 1/2"x24" REBAR, SET IN CONCRETE IN A C-I MONUMENT BOX.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- BRANCH COUNTY REMONUMENTATION CAP, ON REBAR IN CONCRETE, IN C-I MONUMENT BOX:
- SOUTH 05 WEST 46.93' - 18" WALNUT.
  - SOUTH 65 W ST 33.98' - 15" WALNUT.
  - NORTH 10 EAST 27.76' - 30" WALNUT.
  - NORTH 02 WEST 27.80' - CENTER OF 8" DIA. STEEL POST.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON Aug 9, 2000.  
E.R. Reed.  
E.R. REED, Co. Rep.

Signed by Edward R. Reed  
EDWARD R. REED, P.S.  
Surveyor's Michigan License No. 7437



Date APRIL 25, 2000