

BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
 Filing Requirement of Act 74, Mich. P.A. 1970 Branch County
 Recorded

SECTION

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #
<u>MATTESON TWP.</u>	T <u>6</u> S R <u>8</u> W	<u>J-05</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

12-30-1999 11:02:57

Linda Lee Morrison-Mathews
 REGISTER OF DEEDS

Liber **00004** Page **0064**

Register of Deeds Stamp & File Number

MATTESON TWP.

I, Edward R. Reed, P.S. in a field survey on December 1, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented; recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: G.L.O. Fieldnotes of Wm. Brookfield, D.S.: "West corrected between Sec's. 11 & 14 - 40.10 1/2 Set qr. Sec. post".

1969: G. E. Anderson, MSHD: " Re-established on line and midway between N.E. and N.W. corners of Section 14. Set 3/4" pipe in Monument Box. (On a survey by MSHD for Highway M-86).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


From witnesses of G.E. Anderson, dug and found the pipe in Monument Box, in gravel road.

Set a Branch County Remonumentation Cap on 1/2"X18" rebar rod and cemented same in the 3/4" pipe, in C-I monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Branch County Remonumentation Cap on rebar rod in pipe, in C-I monument box:

N 75 E 61.71' Tag in 22" Oak
 N 45 W 35.5' Tag in 30" Walnut.
 S 60 W 53.6' 10" twin Ash.
 South 21.1' Center 12" ASH.



ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-07-99

E. R. Reed, P.S.
 E. R. REED

Signed by Edward R. Reed

Date December 1, 1999

Surveyor's Michigan License No. 7437