

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

BRANCH COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for BRANCH, Located In, Corner Code, and numbered items 1-5.

STATE OF MICHIGAN Branch County Recorded

10-22-1997 09:57:07

Linda Lee Morrison-Mathews REGISTER OF DEEDS

Liber 00003 Page 0168

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, EDWARD W. REED, in a field survey on JULY 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: CORNER COMMON TO SECTIONS 31-14-23-24

- 1826: WM BROOKFIELD, DEPT SURVEYOR - SET CORNER
1969: G. ANDERSON, SURVEY CHIEF, STATE HIGHWAY DEPT, DUG HOLE AND FOUND NO EVIDENCE OF CORNER, RE-ESTABLISHED BY DOUBLE PROPORTIONATE METHOD FROM CORNERS N-E-S-W. PLACED 3/4" X32" PIPE IN MONUMENT BOX.
1976: E.R.REED, CO SURVEYOR - FOUND 3/4" PIPE IN MONUMENT BOX, RECORDED IN LCRC # 179

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET 1/2"X18" REBAR IRON AND REMON CAP INSIDE OF 3/4" PIPE IN CI-MONUMENT BOX.

- P. POLE, S50W 80.67'
10" MAPLE, SOUTH 100.69'
12" OAK, N10W 37.80;
12" MAPLE, N35E 47.85'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER


Signed by Edward W. Reed Date JULY 18, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97

E.R.Reed, P.S. Co. Rep. E.R. REED



1971

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28 REVISED MAY 14, 1975

REVISED JAN. 198 REVISED OCT., 199