

SURVEY & REMONUMENTATION

FEB 13 2001

SECTION

BRANCH COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN Branch County Recorded

09-26-2000 10:17:59

Linda Lee Morrison-Mathews REGISTER OF DEEDS

Liber 00004 Page 0104

Register of Deeds Stamp & File Number

For corners In

BRANCH

Located In:

Corner Code ##

(County)

MATTESON TWP.

1. Public Land Survey

T 6 S R 8 W

M - 07

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (6,5) contains '5'. Cell (7,13) contains a black dot.

MATTESON TWP., T6S, R8W

I, EDWARD R. REED, P.S. in a field survey on APRIL 25, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825: G.L.O. FIELDNOTES OF JOHN MULLETT, D.S.: "SET POST COR. SEC'S 13 & 24".

1969: G.E. ANDERSON, MSHD: "FOUND BROKEN TILE AND STONE CLUSTER 2' BELOW THE GRAVEL SURFACE OF PARHAM RD. IN LINE WITH A FE. TO THE WEST. RAISED TO 1/2' BELOW THE SURFACE WITH A 3/4"x32" PIPE IN MON. BOX. PLACED BROKEN TILE IN MON. BOX."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND THE PIPE IN THE MONUMENT BOX, 18" BELOW ROAD SURFACE. SET BRANCH COUNTY REMONUMENTATION CAP ON 1/2"x18" REBAR, IN CONCRETE IN PIPE. ALL IN C-1 MONUMENT BOX.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 368 OF 1990 AT A MEETING HELD ON

AUG 9, 2000

E.R. Reed, E.R. REED Co. Rep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENTATION CAP, ON REBAR, IN PIPE IN CONCRETE, IN C-1 MONUMENT BOX:

- NORTH 30 EAST 56.91' - NEAR FACE OF POWER POLE.
NORTH 65 EAST 18.5' - TOP CENTER, EAST END OF CMP DRAIN CULVERT.
NORTH 50 WEST 16.9' - TOP CENTER, WEST END OF CMP DRAIN PIPE CULVERT.
NORTH 101.1' - C/L STATE HWY. M86 PAVEMENT (ON N-S SECTION LINE).
NORTH 52 WEST 98.8' - TOP, SOUTH END CMP CULVERT.

Handwritten signature of Edward R. Reed



Signed by EDWARD R. REED, P.S.

Date APRIL 25, 2000

Surveyor's Michigan License No. 7437