

SECTION

BRANCH COUNTY REMONUMENTATION PROGRAM STATE OF MICHIGAN
LAND CORNER RECORDATION CERTIFICATE Branch County
Filing Requirement of Act 74, Mich. P.A. 1970 Recorded

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #
MATTESON TOWNSHIP	T <u>6</u> S R <u>8</u> W	<u>M-08</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

12-30-1999 11:03:04

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0065**

Register of Deeds Stamp & File Number

I, Edward R. Reed, P.S. in a field survey on December 2, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

MATTESON TWP.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: G.L.O. Fieldnotes of John Mullet, D.S. : "40.00 set qtr sec post".
- 1969: G. E. Anderson, MSJD, for Highway M-86 survey: "Re-established on line with the S.E. co. Sec. 24 and the N.E. cor. Sec. 24 and midway between. Set 3/4"X30" black pipe in mon box." (Anderson had 4 witnesses).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

From existing witnesses of Anderson's survey, found the pipe in monument box, about 14" below road surface and 6 ft. west of C/L of gravel road.
Placed a Branch County Remonumentation Cap on 1/2"X18" rebar rod and cemented same in the pipe, all in C-I monument box.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-07-1999

E. R. Reed, P.S.
E. R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Branch County Remonumentation Cap on 1/2" rebar rod in pipe, in C-I monument box:
- N 76 W 20.9' - Center of 30" Oak stump.
- N 30 W 37.0' Center of 20" double maple.
- S 38 E 47.3' Center, top, E. end CMP culvert.
- S 32 W 40.4' Top, center, W. end of CMP culvert, in a plastic drop inlet.
- North 164.08' 1/4 corner post for Section 19, Batavia Township.

Signed by Edward R. Reed, P.S. Date December 2, 1999

Surveyor's Michigan License No. 7437

