

**SURVEY &
MONUMENTATION**

JAN 23 1996 **BRANCH COUNTY REMONUMENTATION CORNER**
LAND CORNER RECORDATION CERTIFICATE
COMMISSION **Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Branch _____ ALGANSEE TOWNSHIP	Located in:	Corner Code #
1. Public Land Survey	T <u>7</u> S R <u>5</u> W	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

12-01-1995 10:21:42

Linda Lee Morrison-Matheus
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Libera 00003 Page 0041 L M

2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9	●					
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, Edward W. Reed, in a field survey on September 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Quarter corner common to Sections 19 and 30, Town 7 south, Range 5 West, Algansee Township, Branch County, Michigan.
 1825: Brookfield, corner set
 1860: Knowles, stone 16 and earthen
 1873: Hamilton, found stone
 1874: _____, found stone
 1977: E. R. Reed found stone and brick set 1/2" x 12" iron over stone, recorded #199

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" iron 3" below new road surface as described in #199
 Set remonumentation cap on iron and cast iron box flush with road surface

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Nov. 07, 1995

E.R. Reed Co. Rep.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1/2" rebar as noted above:
 S 50 E 145.35' NW corner house
 S 35 E 42.50' NW corner telephone pedestal
 N 61 W 98.65' center of 30" maple
 N 32 W 116.96' SE corner of building
 Running West Approximately 4' S of centerline road pavement
 N 47 E 39.80' road name sign

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date September 25, 1995
 Surveyor's Michigan License No. 33985