

5496

SURVEY & MONUMENTATION BRANCH COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE

For corners in **JAN 23 1996**

BRANCH _____ Located In: _____ Corner Code # _____
 (County) **COMMISSION**

ALGANSEE TWP.
 1. Public Land Survey T 7S R 5W _____ D-3 _____
 T _____ R _____ _____
 T _____ R _____ _____
 T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____ _____
 in Section S _____ T _____ R _____ _____

3. Miscellaneous S _____ T _____ R _____ _____
 Property in Sec. S _____ T _____ R _____ _____

STATE OF MICHIGAN
 Branch County
 Recorded
 09-28-1995 10:13:19
 Linda Lee Morrison-Mathews
 REGISTER OF DEEDS
 Liber **00003** Page **0008**
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Edward W. Reed, in a field survey on June 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 QUARTER CORNER COMMON TO SECTIONS 5 & 8, T7S, R5W, ALGANSEE TWP., BRANCH COUNTY, MI.
 1825: W. Brookfield, Deputy Surveyor, -set corner
 1875: J. H. Bennett, County Surveyor, found stone well planted
 1909: John J. Cox, County Surveyor, found stone well planted
 1974: E. R. Reed, County Surveyor, -recorded L.C.R.C. #114, found stone-set 3/4" iron pipe on top
 1972: E. R. Reed-survey tied to corner
 1974: E. R. Reed-survey tied to corner.
 1977: Frederick J. Cutcher-survey referenced to N-S 1/4 section line, Section 8, but not tied to section corner
 1993: E. W. Reed-survey tied to corner
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod marked 14100-32339 (MOSTROM)
 Set cast iron monument box and 1/2" iron and remonumentation cap

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-13-95
E.R. Reed Co. Rep.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 W 24.8'-to near face of 10" square anchor post
 S88°W 28.7'-to near face of power pole
 N52°W 28.5'-to near face of railroad tie anchor post
 S84°E 52.3'-to near face of 10" twin ash

And is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by Edward W. Reed Date June 20, 1995
 Surveyor's Michigan License No. 33985