

SURVEY & REMONUMENTATION

FEB 13 2001

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

SECTION

12-15-2000 14:09:56

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
ALGANSEE TWP		
1. Public Land Survey	<u>T 7 S R 5 W</u>	<u>E-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber **00004** Page **0141**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY REFR GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON 11-28-2000

E.R. Reed P.S.
E.R. REED, Co. Rep.

I, EDWARD W. REED, in a field survey on OCT. 20, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

^{CORNER 12}
QUARTER COMMON TO SECTIONS 16 & 17, ALGANSEE TWP., BRANCH COUNTY, MI

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: WM. BROOKFIELD-CORNER SET
1891: BENNETT-FOUND BOTH U.S. TREES & OLD STAKE HOLE-SET STONE WITH BROKEN TILE & BRICK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

AT DEPTH OF 24", FOUND STONE & BRICK
SET 1/2 X 18" REBAR IRON WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE
IN LINE WITH REMAINS OF FENCE RUNNING NORTH & SOUTH
4" BOX ELDER N55W 81.8'
SOUTH END 24" FIELD DRAIN N75W 128.22'
NAIL & TAG NORTH SIDE OF POWER POLE S8W 232.70'
1 1/4 WELL PIPE S9E 30.41'
CENTER OF SECTION EAST 2,620.30

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED

Surveyor's Michigan License No. 33985



DATED: OCT. 20, 2000

NOTICE
THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAPS ONLY. THIS COPY NOT TO BE REPRODUCED OR SENT PUBLIC TO REGISTER OF DEEDS FOR COPIES.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993
REVISED OCT., 1995