

MAR 21 1997

COMMISSION

BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BRANCH <small>(County)</small>	Located In:	Corner Code #
ALGANSEE TWP.		
1. Public Land Survey	T <u>7S</u> R <u>5W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 00003 Page 0057

STATE OF MICHIGAN
Branch County
Recorded

10-30-1996 09:13:01

Linda Lee Morrison-Mathews
REGISTERED DEEDS CLERK & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Edward W. Reed, in a field survey on JUNE 26, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER COMMON TO SECTIONS 3 AND 4, ALGANSEE TWP., T7S, R5W, BRANCH COUNTY, MI
1825: W. BROOKFIELD, DEP. SURVEYOR, SET CORNER
1970: E.R. REED, COUNTY SURVEYOR-FIELDNOTES INDICATE IRON STAKE
1985: E.R. REED, COUNTY SURVEYOR, FOUND 3/4" IRON STAKE IN CAST IRON BOX, RECORDED IN L.C.R.II-0075

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 1/2" IRON IN MONUMENT BOX 0.8" DEEP
SET REMONUMENTATION CAP ON IRON
RAISED TO ROAD SURFACE WITH 3 LARGE RINGS

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Oct. 9, 1996

E.R. Reed, Cor. Rep.
E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" IRON WITH REMONUMENTATION CAP IN CAST IRON BOX
E 21.0' C/L OF N-S BLACKTOP
S10W 49.3' TO CENTER OF 24" MAPLE
N40W 52.6' TO FACE OF POWER POLE
N75E 67.5' TO FACE OF TELEPHONE PEDESTAL
S20E 103.8' TO FACE OF TELEPHONE PEDESTAL



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date JUNE 26, 1996
Surveyor's Michigan License No. 33985