

**SURVEY & REMONUMENTATION**

FEB 08 1999

**BRANCH COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
ALGANSEE TWP		
1. Public Land Survey	<u>T 7 S R 5 W</u>	<u>H-01</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN  
Branch County  
Recorded

12-07-1998 13:55:13

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on AUGUST 18, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.**

**NORTH QUARTER CORNER, SECTION 3**

A. Description of original monument and accessories and/or subsequent restoration:

1825: WM. BROOKFIELD, DEPT SURVEYOR - CORNER SET  
NO OTHER EVIDENCE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG LARGE HOLE WITH BACKHOE, FOUND POINTED STONE SURROUNDED BY BRICK

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON IN PLACE OF STONE, WITH REMON CAP IN CI-MONUMENT BOX

IN LINE WITH FENCE RUNNING SOUTH  
FACE OF WOOD ANCHOR POST, SOUTH 24.72'  
TEL PED N60E 198.80'  
NAIL & WASHER N SIDE 18" WALNUT S20W 25.73'  
NAIL & WASHER N SIDE 18" WALNUT S55W 52.49'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed  
EDWARD W, REED

Date NOV. 4, 1998

Surveyor's Michigan License No. 33985

Liber 00003 Page 0262

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-04-1998

E.R. Reed Co. Rep.  
**E.R. REED**

