

For corners in

<u>Branch</u> (County)	Located In:	Corner Code -#
Alganssee Twp.		
1. Public Land Survey	T <u>7</u> S R <u>5</u> W	<u>T-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section .	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF NICHIGAN
~~Recorded~~
 STATE OF NICHIGAN
 Branch County
 Recorded
 12-01-1995 10:24:34
 Register of Deeds Stamp & File Number
 Linda Lee Morrison-Matthews
 REGISTER OF DEEDS

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Edward W. Reed, in a field survey on September 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner common to Sections 2, 3, 11 and 10, of Town 7 South, Range 5 West, Alganssee Township, Branch County, Michigan.
 1825: brookfield, corner set
 1878: Knowles, found stone
 1979: E. R. Reed, found small stones and broken brick, set 1/2" iron, recorded #234
 1994: E. W. Reed, found iron, used in survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" rebar as recorded in #234
 Set remonumentation cap and cast iron box flush with road surface

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Nov. 07, 1995
E. R. Reed Co. Rep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner
 1/2" rebar as noted above:
 S 52 W 39.2' square wood post
 North 29.4' 2" iron post in concrete base
 N 56 W 53.2' to corner of telephone pedestal
 S 55 E 39.7' center S end CMP
 3.1" S of centerline road East-West



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date September 25, 1995
 Surveyor's Michigan License No. 33985