

**SURVEY &
REMONUMERATION**

FEB 08 1999

SECTION

**BRANCH COUNTY REMONUMATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
ALGANSEE TWP		
1. Public Land Survey	T <u>7</u> S R <u>5</u> W	<u>J-01</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

12-07-1998 13:55:20

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Liber **00003** Page **0263**

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCTOBER 22, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NORTH QUARTER CORNER, SECTION 2

A. Description of original monument and accessories and/or subsequent restoration:

1825: WM BROOKFIELD, DEPT, SURVEYOR - CORNER SET
NO OTHER CORNER EVIDENCE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG LARGE HOLE WITH BACKHOE, FOUND POINTED STONE WITH BRICK.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ½" X 18" REBAR IRON WITH REMON CAP IN PLACE OF STONE, SET CI-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

SPIKE & WASHER IN S. SIDE POWER POLE,	N 61 W	73.15'
SW CORNER TEL PED.	N 22 W	32.50'
WEST SIDE RR TIE ANCHOR POST	N 83 E	51.15'
(NORTH 1 OF 2)		
QUINCY CORNER (J 13)	EAST	34.04'
C/L NORTH-SOUTH ROAD	EAST	18.0'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W, REED

Date NOV. 4, 1998

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-04-1998

E.W. Reed Co. Rep.
E.R. REED

