

SURVEY & REMONUMENTATION

FEB 13 2001

SECTION

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
Branch County
Filing Requirement of Act 74, Mich. P.A. 1970
Recorded**

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
<u>ALGANSEE TWP</u>		
1. Public Land Survey	<u>T 7 S R 5 W</u>	<u>M-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>

12-15-2000 14:10:18

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0143**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E. R. Reed, P.S.
E. R. REED, Co. Rep.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCT. 20, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHEAST CORNER SECTION 12 AND NORTHEAST CORNER OF SECTION 13, ALGANSEE TWP., BRANCH COUNTY, MI

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: MULLETT-CORNER SET
1957: BROOKFIELD-SUBDIVISION OF TWP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER NOW GONE-POINT IS UNDER ROCK & RUBBLE PILE WHERE LAND OWNER HAS PUSHED UP STONE & FENCE ROW RESET CORNER USING K-5 & L-5 OF BRANCH AND B-5 & C-5 OF HILLSDALE & GLO OFFSET SET 1/2" X 18" REBAR IRON WITH REMON CAP SET CARSONITE MARKER ALONG SIDE


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP		
HILLSDALE CORNER A-5	NORTH	69.3'
CENTERLINE OF EAST-WEST ROAD	NORTH	35'
ROUND CONCRETE ANCHOR POST	N74E	328.79'
CENTER OF 60" OAK	N70E	294.8'
POWER POLE	NORTH	159.68'
CENTER OF TRIPLE BOX ELDER	S3W	41.4'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W. REED

Surveyor's Michigan License No. 33985



BRANCH COUNTY DEPARTMENTAL USE
FOR BRANCH COUNTY DEPARTMENTAL USE ONLY. THIS FORM NOT TO BE REPRODUCED.
SEND PUBLIC TO REGISTER OF DEEDS FOR COPIES.
DATED: OCT. 20, 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1995