

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
Filing Requirement of Act 74, Mich. P.A. 1970 Branch County

For corners in

| | | | |
|---------------------------------------|---------------------------|---------------|--|
| <u>BRANCH</u> (County) | Located In: | Corner Code # | |
| <u>OID TOWNSHIP</u> | | | |
| 1. Public Land Survey | T <u>7</u> S R <u>6</u> W | <u>A - 5</u> | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

Recorded

10-22-1997 09:57:14

Linda Lee Morrison-Mathews
 REGISTER OF DEEDS

Liber **00003** Page **0169**

Register of Deeds Stamp & File Number

OID TOWNSHIP

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, EDWARD R. REED, in a field survey on JULY 03, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: G.L.O. FIELDNOTES OF WM. BROOKFIELD, D.S. = "81.20 INTERSECT W BOUND LINE 99 LKS S OF COR POST & SET POST COR SECS 7 & 18. BEECH 9 N85½E 28 W OAK 20 S32E 55".
- 1875: J. H. BENNETT, CO. SURVEYOR - "SEC. COR. FOR OVID 99 LKS S OF BETHEL CORNER. PLANTED STAKE, STONE & BRICK"
- 1889: HAMILTON, CO. SURVEYOR = "FD STONE CENTER OF HIGHWAY"
- 1976: E. R. REED, CO. SURVEYOR - L.C.R.C. 1/190 = FD. LARGE FLAT STONE 14" BELOW GRADE SURFACE.
- 1982: E. R. REED - SURVEY REFERENCED TO CORNER STONE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND LARGE FLAT STONE AS IDENTIFIED ON L.C.R.C. 1/190, AND SURVEYS IN IN 1976 & 1982. STONE HAS A DRILL HOLE IN CENTER OF STONE, AND A PAINTED CIRCLE AROUND DRILL HOLE. DRILLED A 2" DEEP HOLE IN STONE AND CEMENTED A 1/2" x 8" STEEL REBAR ROD IN STONE, WITH A BRANCH COUNTY REMONUMENTATION CAP ON TOP OF ROD. PLACED MONUMENT BOX (RINGS) AROUND REBAR ROD; WITH CONCRETE AND ASPHALT AROUND ROD AND BOX. TOP OF BOX IS 3 INCHES BELOW GROUND SURFACE. PLACED CARSONITE "SURVEY MARKER" ON EAST SIDE OF BOX.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STEEL REBAR WITH BRANCH COUNTY REMONUMENTATION CAP OVER STONE, IN C-1 MONUMENT BOX:

- N 47 W 41.6' - NEAR FACE OF P. POLE.
- S 27 W 113.9' - CENTER OF 42" OAK.
- EAST 58.3' (ON SEC. LINE) - C/L BEHNKE ROAD
- NORTH 65.34 - N.E. CORNER SECTION 13, BETHEL TWP.
- S 07 E 105.3' - NEAR FACE OF P. POLE.
- S 60 E 89.4' - CENTER OF 30" SPRUCE TREE.
- NORTH 57.0' - C/L CENTRAL ROAD.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97

E.R. Reed, Rep.
 E.R. REED, P.S.

Signed by [Signature]
 Surveyor's Michigan License No. EDWARD R. REED, P.S. 7437



Date JULY 03, 1997