

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BRANCH (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>6W</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
John J. Johnson
 MAR 10 AM 9:48
 REC'D FOR RECORD
 STATE OF MICHIGAN
 BRANCH COUNTY

II 284

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EDWARD W. REED, in a field survey on JANUARY 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8: WEST QUARTER CORNER SECTION 19, OVID TOWNSHIP, T7S, R6W.

Old section corner record file - "Stone on edge surrounded by brick.

E. R. REED, COUNTY SURVEYOR: Found stone 1 1/2' deep, set iron on top.
 JAMES L. KING, RLS: (5-18-73) Found 1/2" iron stake.
 REFERENCED TO THE PLAT OF "SUNNY SHORES"
 REFERENCED TO THE PLAT OF "MELODY SHORES"


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod fitting old witness of Reed & King.

Set "BRANCH COUNTY REMONUMENTATION MARKER" on 1/2" iron and placed CI-Monument box over and level with road surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Capped rebar iron in monument box:
 S 22 E 97.35', NW corner house
 N 40 E 39.5', Power Pole
 S 21 W 103.4', Telephone pedestal
 N 49 W 65.7', 8" Maple
 N 16 W 74.7', 2" Pine



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *Edward W. Reed* Date JANUARY 24, 1994
 Surveyor's Michigan License No. 33985