

SURVEY & REMONUMENTATION

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT MEETING HELD ON 12-16-94

APR 26 1995
BRANCH COUNTY MONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
COMMISSION

For corners in Ed Reed Co. Rep.

Branch <small>(County)</small>	Located in:	Corner Code #/4
1. Public Land Survey	T <u>7</u> S R <u>6</u> W	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

12-28-1994 15:07:00

Libra 00002 of 0331
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward W. Reed, in a field survey on September 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 31 and 32, Town 7 South, Range 6 West, Ovid Township and Sections 5 and 6, Town 7 South, Range 6 West, Kinderhook Township, Branch County, Michigan.

1825: GLO-corner set

1872: Bennett, found stone

1974: E. R. Reed, found stone and 2 pieces of iron rod 12" long 14" below grade

1978: Cutcher found iron and stone

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found two small iron rods over pointed stone

Set 1/2" x 12" iron bolt and remonumentation cap on top of stone

Set cast iron monumentation box 1 1/2" below gravel road surface



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 72 West 78.3'-12" hickory

South 41 East 50.44'-nail and washer 1' up North side of 30" maple

North 80 East 133.48'-nail and washer 1' up South side of 32' maple

South 30 East 58.85'-nail and washer 1' up North side of 30" maple

North 47 West 210.00'-nail and washer 1' East side of power pole

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date September 28, 1994
Surveyor's Michigan License No. 33985