

COMMISSION BRANCH COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: BRANCH (County), Located In:, Corner Code --. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

267

Vertical stamps: REGISTER OF DEEDS, 93 DEC 27 AM 10:07, REC'D FOR RECORD STATE OF MICHIGAN BRANCH COUNTY

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column E and row 2.

OVID TWP., T7S, R6W

I, EDWARD R. REED, in a field survey on NOVEMBER 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: SECTION CORNER 4-5 ON NORTH TOWNSHIP LINE OF T7S, R6W. GLO = NOV. 1825 - W. BROOKFIELD, SEP. SURVEYOR: "N BETWEEN SEC 4 & 5, 80.29 INTERSECT N BOUND LINE 29 LKS W OF COR POST & SET POST COR SEC'S 4 & 5. BEECH 7 S17E 12, SYCAMORE 18 S60W 27." 5/31/1878 - L2/98, CO. SURVEYOR'S RECORDS: M. KNOWLES, CO. SURVEYOR: "E - FD TWO STONES & STAKE BETWEEN. SET A BRICK ABOVE THE STAKE & STONES AROUND." REF. CORNER: 10/22/1979 - E. R. REED, CO. SURVEYOR: "CORNER TO SEC'S. 32-33, T6S, R6W, COLDWATER TWP. IRON OVER STONE. WOOD POST N 30.4', IRON POST S58W 50.7', P. POLE S16E 64.8'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PILE OF STONES AND PIECES OF BROKEN BRICK AT DEPTH OF 26" BELOW ROAD SURFACE IN ORIGINAL SOIL; (FOUND NOTHING BELOW THIS); AND AT APPROXIMATE GLO DISTANCE FROM CORNER 32-33, T6S, R6W; ACCEPTED THIS MONUMENT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER; AND SET A 1/2" x 18" REBAR STEEL ROD WITH I.D. CAP # 7437 IN MONUMENT BOX AT THIS LOCATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1: SECTION CORNER 4-5, ON NORTH TOWNSHIP LINE, T7S, R6W, OVID TWP. 1/2" x 18" REBAR STEEL ROD WITH I.D. CAP #7437, IN MONUMENT BOX, 2' S. OF C/L ROAD. S 40 W 36.9' TO L-IRON ANCHOR POST. N 70 E 70.30' TO SPOTTER, S. SIDE OF 14" ELM. S 30 E 73.7' TO NEAR FACE OF POWER POLE. S 30 W 55.7' TO TOP CENTER OF TEL. PEDESTAL. N 75 E 83.11' TO NEAR FACE P. POLE (WITH METER BOX). N 40 E 36.10' TO NEAR FACE OF 8" DIA. WOOD POST. EAST 19.20' TO IRON ROD IN MONMENT BOX @ SEC. CORNER 32-33, T6S, R6W. AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Surveyor's Michigan License No. 7437



Date 11/16/93