

# SURVEY & REMONUMENTATION

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1990 AT A MEETING HELD ON 12-16-94

*E.R. Reed, C. Rep.*

APR 26 1995  
BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
**COMMISSION**

For corners in  
BRANCH

(County)	Located In:	Corner Code
OID TOWNSHIP		E-7
1. Public Land Survey	T <u>7</u> S R <u>6</u> W	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
Branch County  
Recorded

12-28-1994 15:07:34

LIBER 00002 0335  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD R. REED, in a field survey on NOVEMBER 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7					●								
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

OID TOWNSHIP, T7S, R6W

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
SECTION CORNER 16-17-20-21, OVID TWP., T7S, R6W.

G.L.O. FIELDNOTES, W. BROOKFIELD, 1825: "80.00 SET POST COR SEC'S 16, 17, 20 & 21. BEECH 12 S48E 54 BEECH 9 S1W 46"

D. WILSON, CO. SURVEYOR, 1848: AT N. SEC CORNER POST NW. (NO MONUMENT DESCRIPTION).

H. CARY, DEP. CO. SURVEYOR, 1856: "ESTABLISHED CORNER.. NEW WIT: BEECH 7 N69½E 80, SUGAR 6 S04E 120." L. 1, PG. 54, CO. SURVEY RECORDS.

E. REED, CO. SURVEYOR, 1972: FOUND IRON PIPE 18"DEEP, (DESCRIBED ON OLD SECTION CORNER FILE CARD); SET 3/4"IRON ROD IN PIPE: S. END CMP CULVERT S42W 31.3'; N. END CMP CULVERT N36W 32.0'; 10" WALNUT N31W 75.15'.

D. BOONE, 1974, L.C.R.C. #134: "FD. 5/8" IRON ROD".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ALL G.L.O. ORIGINAL WITNESSES ARE GONE.

FOUND 3/4" IRON ROD UNDER BLACKTOP PAVEMENT, FROM WITNESSES OF 1972 SURVEY.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

REMOVED 3/4" IRON ROD AND REPLACED WITH 1/2"x18" STEEL REBAR ROD SET IN CONCRETE, WITH REMONUMENTATION CAP, IN C-I MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" STEEL REBAR ROD, WITH BRANCH COUNTY REMONUMENT CAP, IN MONUMENT BOX.

N 88 E 120.63' TO NEAR FACE OF POWERPOLE.

N 28 E 83.35' TO CENTER OF SQUARE TELEPHONE PEDESTAL.

S 84 W 94.38' TO CENTER OF RECTANGULAR TELEPHONE PEDESTAL.

N 08 W 121.22' TO CENTER OF 24" ELM TREE.

S 42 W 31.3' TO CENTER S. END CMP ROAD CULVERT.

N 36 W 32.0' TO CENTER N. END CMP ROAD CULVERT.


AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by

*Edward R. Reed*

Surveyor's Michigan License No. 7437

EDWARD R. REED



Date NOVEMBER 23, 1994